


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J-9

History of original corner establishment:  
Corner originally established 1882 under Contract Survey No. 417, dated 1881.  
Corner re-established by Dependent Resurvey authorized 1938 and approved Feb. 21, 1941.



Description of corner evidence found:  
2 inch iron pipe with 2 1/2 inch brass cap marked as shown above,  
from which---

- 11" Spruce (record 5" Doug Fir), alive and standing, bears N 39° E (record N 40° E) 32.0' (record 31.7'), blaze healed, scar visible.
- 13" White Fir, alive and standing, bears S 62 1/2° E (record S 60° E) 14.5' (record 13.9'), blaze healed, scar visible.
- 11" Tamarack, alive and standing, bears S 56° W (record) 23.8' (record 25.1'), blaze healed, scar visible.
- 11" Tamarack, alive and standing, bears N 34 1/2° W (record N 35° W) 37.3' (record 37.6'), blaze healed, scar visible.
- 6' metal fence post found 4' south of corner with USFS sign 54-4.

Description of monument and accessories | established to perpetuate the original location of this corner:  
Attached USFS signs, 54-4 and 54-3 to all Bearing Trees, painted blazes and a 6" wide band of fluorescent red paint around all trees.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Thomas F. Upton*

OREGON  
FEBRUARY 14 1975  
THOMAS F. UPTON  
1024

Thomas F. Upton, Certificate No. R.L.S. 1024

Office of S.O. Swartz County of Morrow  
State of Oregon, hereby certify that the within instrument was filed in this office  
for record on the 12th day of January, 1982  
Dorinda H. Krumbein by Martha A. Hughes  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

**RECEIVED BY**  
**Morrow County Surveyor**  
Date January 12, 1982  
Rec'd By M. Hughes  
No. 467-K  
Ref. dwg. no. C-459-1c