

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Refer to: Plat of Penland 1988 Cadastral Survey
Sections 11 and 14, T.59., R.28E., W.M.

K-19

History of original corner establishment:
No record of previous monumentation.

DIAGRAM
T5S R28E
C
N1/16 S14
C

Description of corner evidence found:
None.

Description of monument and accessories established to perpetuate the original location of this corner:

At the corner point I set a 2 1/2" x 30" alum. pipe with a 2 1/2" alum. cap

containing a magnet and marked: Monument is 22" in the ground. N1/16 S14 C

From the corner; PLS 1832 1988

A Lodgepole pine, 13" dia., N150W, 33.8 ft.; marked: C/N1/16 S14 BT

A White Fir, 15" dia., N35 1/2 E, 19.9 ft.; marked: C/N1/16 S14 BT
BTs have blaze and a 6" band painted red, BT tags, "Land Survey Monument" signs and alum. "PLS 1832" washers nailed to the bottom of the blaze. There is a 6' steel fence-post with a "Land Survey Monument" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 18 3/4 E.
July 27, 1988

RECEIVED BY

Morrow County Surveyor

Date 11/188
Rec'd By OHK
No. G 8721K

REGISTERED PROFESSIONAL LAND SURVEYOR

Office of..... County of.....
State of..... I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... (COUNTY OFFICIAL) by (DEPUTY)

<i>[Signature]</i>
OREGON JULY 13, 1979 FAYETTE S. MUNRO 1832