

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index: L-13

Quarter corner secs. 15 & 16, T.55., R.28E., W.M.			
Original survey of township by Sanderson in 1831.	1	DIAGRAM	1
His record reader: Set 6x10x16 sandstone from which:	1		1
A 16" tamarack bears N20°N, 40 lks.	1		1
A 12" fir bears S15°E, 18 lks.	1	1/4	1
Township retraced by Carter of GLO in 1938.	1	S16 1 S15	1
His record reader: Set an iron post 3 ft. long, 1 in.	1	1938	1
diam., 27 ins. in the ground for 1/4 sec. cor., with	1		1
brass cap nkd. (see diagram) from which:	1		1
A 8" white fir bears N85°E, 8 lks.	1		1
A 11" tamarack bears S71°W, 11 lks.	1		1

Description of corner evidence found:

Found the iron post with standard GLO brass cap stamped as shown in the diagram, from which:

A 15" dbh white fir bears N85°E, S.3' with healed blaze.

Description of monument and accessories I established to perpetuate the original location of this corner:

The bearings were based on the surveyed bearing between the NE corner and the East 1/4 corner of section 16 as recorded in by PLS 1638 in Morrow County survey 269-K. I set the following new witness tree:

A 21" dbh Tamarack bears N82°46'E, 56.2' scribbled 1/4 S15 BT;

A 14" dbh Tamarack bears S14°25'E, 44.2' scribbled 1/4 S15 BT;


A 11" dbh Engelman Spruce bears S48°20'N, 41.3' scribbled 1/4 S16 BT;

A 9" dbh Tamarack bears N56°41'W, 47.8' scribbled 1/4 S16 BT;


An aluminum washer stamped PLS 852 is nailed between the letters B and T on the new trees. All the BT's have LSM and BT signs attached.

Painted 6" red bands around all the trees and painted the scribe blazes red.

This work was done September 25, 1992.



David L. Haddock



Office of _____ County of _____
 State of _____, I hereby certify that the within instrument was filed
 in this office for record on the _____ day of _____, 19____.
 _____ (COUNTY OFFICIAL) by _____ (DEPUTY)

Form 86-7100-57 (9/71)

RECEIVED BY

Morrow County Surveyor

Date 11/92

Rec'd By MLL

No. _____