

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Refer to: Plat of Penland 1988 Cadastral Survey
Sections 11 and 14, T.55., R.28E., W.M.

L-19

History of original corner establishment:
No record of previous monumentation.

DIAGRAM
T55 R28E
C $\frac{1}{4}$ S14

Description of corner evidence found:
None.

Description of monument and accessories I established to perpetuate the

original location of this corner:

At the corner point I set a 2 $\frac{1}{2}$ " x 30" alum. pipe with a 2 $\frac{1}{2}$ " alum. cap

T55 R28E
C $\frac{1}{4}$ S14
PLS 1832
1988

Monument is 25" in the ground.

From the corner:

A Western Larch, 8" dia., N12 $\frac{1}{2}$ W, 51.9 ft.; marked: C $\frac{1}{4}$ S14 BT
A Spruce, 17" dia., N64 $\frac{1}{2}$ E, 23.1 ft.; marked: C $\frac{1}{4}$ S14 BT

BTs have blaze and a 6" band painted red, BT tags, "Land Survey Monument" signs and alum. "PLS 1832" washers nailed to the bottom of the blaze. There is a 6' steel fence post with a "Land Survey Monument" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 18 $\frac{1}{2}$ °E.
July 27, 1988

RECORDED BY

MARION COUNTY SURVEYOR

Date 11/19/88

Recd By CHIK

No. C 872K

Office of..... County of.....

State of..... I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by

(COUNTY OFFICIAL)

(DEPUTY)

