


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

L-9



History of original corner establishment:
 Corner originally established 1882 under Contract Survey No. 417, dated 1881.
 Corner re-established by Dependent Resurvey authorized 1938 and approved Feb. 21, 1941.

Description of corner evidence found:
 1 inch iron pipe, with 2 1/2 inch brass cap marked as shown above, from which---
 20" Tamarack, dead and down, bears easterly 20', scribing 1/4 S 16 BT legible.
 No evidence of original Bearing Tree for Section 17 found.

Description of monument and accessories | established to perpetuate the original location of this corner:

From Corner location as found and described above,
 New Bearing Tree, 11" White Fir, bears N 42° E a distance of 26.3 feet, which I marked "1/4 S 16 BT".
 New Bearing Tree, 11" White Fir, bears N 82° W a distance of 12.6 feet, which I marked 1/4 S 17 BT.
 Attached USFS signs 54-4 and 54-3 to all Bearing Trees, and painted blazes and a 6" wide band of fluorescent red paint around all trees.
 Attached brass tag, marked R.L.S. 1024, to new Bearing Trees.
 Set 6' steel fence post 5' North of Corner and attached USFS signs, 54-2 over 54-4.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR
 Thomas F. Upton
 OREGON
 FEBRUARY 14 1975
 THOMAS F. UPTON
 1024

Thomas F. Upton, Certificate No. R.L.S 1024

Office of CO SURVEYOR County of MORROW
 State of Oregon, hereby certify that the within instrument was filed in this office
 for record on the 12th day of MARCH, 1982
Thomas H. Kumbaska by Matthew A. Higgins
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Form R6-7100-57 (9/71)

Morrow County Surveyor * GPO-1988-276

Date January 12, 1982
 Rec'd By M. Higgins
 No. 464-K
 Ref. dwg. no. C-459-K