

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

M-16

History of original corner establishment:

Unsurveyed - subdivided Section.

DIAGRAM
T5 S R28 E
SE 1/16 · S15

No record of subsequent remonumentation found in County Records.

Description of corner evidence found:

No evidence found.

I set the monument described below at the point of intersection of the four computed 1/16 corners, CS 1/16, S 1/16, CE 1/16, and E 1/16.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Terry E. Hamby
OREGON
JULY 14, 1988
TERRY E. HAMBY
1638

Description of monument and accessories established to perpetuate the original location of this corner

At the position described above, I set a 2½" x 30" iron pipe 26" in the ground, with a brass cap marked as shown:

From which I scribed BIs:

A fir 13" in diam. bears S 77° E 30.2' marked S E 1/16 S 15 BI.
A fir 11" in diam. bears S 19° W 12.7' marked S E 1/16 S 15 BI.

- nailed a brass washer marked PLS 1638 to the BI blazes.
 - set a steel fence post 10' North and 4' West with signs 54-4.
 - painted a red band around the BIs and face of scribe.
 - used a steel tape and a magnetic compass with 21° east variation and measured a horizontal distance to the center of BIs.
- This corner was set October 20, 1979.
Witness by Dennis L. Paasch and W. Keith Sands.

T5 S R28 E
SE 1/16 · S15
1979
PLS 1638

Office of _____ County Surveyor _____ County of _____ MORROW _____
State of Oregon _____, I hereby certify that the within instrument was filed in this office
for record on the 4th day of Dec. 1979
Dennis L. Paasch by _____ (DEPUTY)
(COUNTY OFFICIAL)

RECEIVED BY
Morrow County Surveyor
Date 12-10-79
Rec'd By WMT
No. 267-R

Reopening drawing