


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N-11

History of original corner establishment:

Corner originally established 1882 under Contract Survey No. 417, dated 1881.

Corner re-established by Dependent Resurvey authorized 1938 and approved Feb. 21, 1941.



Description of corner evidence found:

1 inch iron pipe, with 2 1/2 inch brass cap marked as shown above,
from which---

30" spruce (record 17" White Fir) bears N 29° W (record), 102.3' (record).
Tree alive and standing, blaze healed, scar visible.

30" Tamarack, dead and standing, bears S 6° W (record), 90.4' (record),
scribing 1/4 S21 BT legible.

Note:

Original pipe monument was found lying horizontal at surface of ground. Reset same at location as determined by both Bearing Trees. This location is in washed out portion of small earthen dam. Built mound of stone around pipe monument.

Description of monument and accessories | established to perpetuate the original location of this corner:

From Corner location as described above,

New Bearing Tree, a 14" Spruce, bears S 45 1/2° W, a distance of 40.2 feet, which I mark 1/4 S21 BT.

Attached USFS signs, 54-3 and 54-4, to all Bearing Trees, and attached brass tag, marked R.L.S. 1024, to new Bearing Tree. Painted blazes and a 6" wide band around trunks of all trees.

Set 6' steel fence post 5' East of corner and attached USFS sign 54-4.

REGISTERED PROFESSIONAL LAND SURVEYOR <i>Thomas F. Upton</i>	OREGON FEBRUARY 14, 1975 THOMAS F. UPTON 1024
---	--

Thomas F. Upton, Certificate No. R.L.S. 1024

Office of Co. Surveyor County of MORROW
 State of Oregon I hereby certify that the within instrument was filed in this office
 for record on the 12th day of January 1982
David W. Krumhain by Myrtha A. Hughes
 (COUNTY OFFICIAL) (DEPUTY)

FORM R6-7100-57 (9/71)

RECEIVED BY

Morrow County Surveyor

Date January 12, 1982

Rec'd by M. Hughes

L.O. 472-K

Ret. David W. Krumhain