

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Refer to: Plat of Penland 1988 Cadastral Survey
Section 22, T.5S., R.28E., W.M.

O-14

History of original corner establishment:
No record of previous monumentation.

DIAGRAM
T5S R28E
NW1/16 S22

Description of corner evidence found:
None.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the corner point I set a 2 1/2" x 30" alum. pipe with a 2 1/2" alum. cap

NW1/16 S22
PLS 1832
1988

Monument is 24" in the ground.

From the corner:

A Spruce, 21" dia., 586 1/2 W, 23.7 ft.; marked; NW1/16 S22 BT
A Spruce, 23" dia., N28 0 E, 34.0 ft.; marked; NW1/16 S22 BT

BTs have blaze and a 6" band painted red, BT tags, "Land Survey Monument" signs and alum. "PLS 1832" washers nailed to the bottom of the blaze. There is a 6' steel fence-post with a "Land Survey Monument" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 18 1/2 O E.
September 1, 1988

RECEIVED BY
Morrow County Surveyor

Date 11/88
Rec'd By LOHAK
No. D874K

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Fayette S. Munro
OREGON
JULY 13, 1979
FAYETTE S. MUNRO
1832

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... (COUNTY OFFICIAL) by (DEPUTY)