

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Refer to: Plat of Penland 1988 Cadastral Survey
Section 22, T.53., R.28E., W.M.

P-15

History of original corner establishment:
Donald L. Staebler, RPE 5408, set an iron pin during
a survey in 1972.

DIAGRAM
T55 R28E
C1 522

Description of corner evidence found:

From the corner point:
A 3/4" dia. iron rod (rebar) bears N48°E, 1.2 ft.

Description of monument and accessories | established to perpetuate the original location of this corner:
At the corner point I set a 2 1/2" x 30" alum. pipe with a 2 1/2" alum. cap
containing a magnet and marked:

T55 R28E
C1 522
PLS 1832
1988

Monument is 22" in the ground and surrounded
by a mound of stone.

From the corner:

A Spruce, 11" dia., S52 1/2° E, 13.2 ft.; marked: C1 522 BT
A Spruce, 20" dia., N41° E, 39.6 ft.; marked: C1 522 BT

BTs have blaze and a 6" band painted red; BT tags, "Land Survey Monument"
signs and alum. "PLS 1832" washers nailed to the bottom of the blaze.
There is a 6' steel fence-post with a "Land Survey Monument" sign within
5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic
declination set at 180E.

September 1, 1988

RECEIVED BY
Morrow County Surveyor

Date 11/28
Rec'd By LOHK
No. D 874K

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Fayette S. Munro
OREGON
JULY 10, 1973
FAYETTE S. MUNRO
1832

Office of..... County of.....

State of..... I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)