

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index: P-17

Boundary corner sections 22 and 23, T.55., R.22E., W.M.			
Corner first set by Sanders in 1881.	1	DIAGRAM	1
His record reads: Set a post 9" square, 9' long, 24"	1	158 203E	1
in the ground, from corner:	1		1
A black pine, 10" dia., 850°N, 19 1ks.	1	1/4	1
A pine, 8" dia., 810°N, 21 1ks.	1	822 1 823	1
Township retraced by Carter of GLO in 1938.	1		1
His record reads: found original post and radiated	1	1938	1
it with a 1" x 36" iron post with a brass cap marked:	1		1
(see diagram). From the corner:	1		1
A White Fir, 20" dia., 860°E, 21 1ks. (with heated glass, (old BT))	1		1
A Spruce, 28" dia., 820°E, 22 1ks. (new BT)	1		1

In 1938, PLS 1832 maintained this corner. His record reads:
 Built a mound of stone around the corner, marked a new BT.
 A White Fir, 20" dia., 845 3/4°N, 25.1 1ks.; marked 1/4 822 BT.

Description of corner evidence found:
 Found the iron post as described with standard GLO brass cap stamped as
 shown in the diagram, from which:
 A 32" DBH Western Larch stand bears S24°01'N, 14.4' with heated glass.
 A 32" DBH White Fir bears S59°19'E, 14.2' with heated glass.
 A 15" DBH White Fir bears S49°59'E, 25.0' with visible scarfs.

Description of monument and accessories I established to perpetuate the
 original location of this corner:
 The bearings were based on the surveyed bearing between this 1/4 corner
 and the section corner of sections 22, 23, 26 and 27 as recovered by
 PLS 1838 in Morrow County survey D-252-K.

I set the following new witness trees:
 A 8" DBH Engelman Spruce bears N54°50'N, 15.1' marked 1/4822BT
 A 12" DBH Western Larch bears N70°47'E, 56.3' marked 1/4823BT
 An aluminum washer stamped PLS 852 is nailed between the letters B and T
 on the new trees. All the BTs have LSM and BT signs attached.
 Painted 6" red bands around all the trees and painted the
 white stakes red.

**REGISTERED
 PROFESSIONAL
 LAND SURVEYOR**

David L. Haddock

**OREGON
 JULY 12, 1958
 DAVID L. HADDOCK
 852**

Office of _____ County of _____
 State of _____ I hereby certify that the within instrument was filed
 in this office for record on the _____ day of _____, 19____
 by _____ (DEPUTY)