

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

Refer to: Plat of Stahl 1990 Cadastral Survey  
Section 26, T.5S., R.28E., W.M.

*R12-19*

History of original corner establishment:  
No record of previous monumentation.

**DIAGRAM**  
T59 R28E  
C-N-N 1/64  
S26

Description of corner evidence found:  
None..

Description of monument and accessories | established to perpetuate the original location of this corner:

At the corner point established by measurement, I set a 2 1/2" x 30" alum. pipe with a 2 1/2" alum. cap mkd.:  
The monument is 22" in the ground and surrounded by a mound of stone.  
From the corner:  
A Douglas Fir, 20" dia., S64 1/2° 10'E, 108.3 ft. ;  
mkd.: CNN 1/64 S26 BT  
A Ponderosa Pine, 20" dia., S64 1/4° 0'W, 84.6 ft. ;  
mkd.: CNN 1/64 S26 BT

BTs have blaze and a 6" band painted red, BT tags, "Land Survey Monument" signs and alum. "PLS 1832" washers nailed to the bottom of the blaze. There is a 6' steel fence post with a "Land Survey Monument" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 19°E.

July 27, 1990



Office of..... County of.....  
State of..... I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by ..... (DEPUTY)  
(COUNTY OFFICIAL)

Form R6-7100-57 (9/71)

RECEIVED BY

Morrow County Surveyor

Date 1/9/91

Rec'd by RL

No. C 903

R12-19