

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Refer to: Plat of Stahl 1990 Cadastral Survey
Section 26, T.5S., R.28E., W.M.

R 1/2-21

History of original corner establishment:
No record of previous monumentation.

DIAGRAM
T5S R28E
N-N 1/64
S26 | S25

Description of corner evidence found:
None..

Description of monument and accessories | established to perpetuate the original location of this corner:

At the corner point established by measurement, I set a 2 1/2" x 30" alum. pipe with a 2 1/2" alum. cap mkd.:
Monument is 23" in ground.

N-N 1/64
S26 | S25
PLS 1832
1990

From the corner:
A Spruce, 14" dia., N48°W, 70.6 ft.;

mkd.: NN 1/64 S26 BT

A Spruce, 16" dia., N190°E, 58.9 ft.;

mkd.: NN 1/64 S25 BT

BTs have blaze and a 6" band painted red, BT tags, "Land Survey Monument" signs and alum. "PLS 1832" washers nailed to the bottom of the blaze. There is a 6' steel fence post with a "Land Survey Monument" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 190°E.

July 26, 1990



Office of..... County of.....
State of..... I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... (COUNTY OFFICIAL) by (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Morrow County Surveyor

GPO-799-276

Date 7/21
Rec'd by DE
No. C-903 R 1/2-21