

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R-13

History of original corner establishment:

Corner originally established 1882 under Contract Survey No. 417, dated 1881.

Corner re-established by Dependent Resurvey authorized 1938 and approved Feb. 21, 1941.

DIAGRAM	
T55	R28E
21	22
28	27
1938	

Description of corner evidence found:

2 inch iron pipe with a 2 1/2 inch brass cap, marked as shown above, from which ---

20" White Fir, alive and standing but with top split, bears N 14° E (record) 40.9' (record) blaze healed but scar visible.

20" White Fir, alive and standing, bears S 49° E (record) S 51° E) 42.6' (record) blaze healed but scar visible.

32" White Fir, alive and standing, bears S 54° W (record) 21.4' (record) 21.8') blaze healed but scar visible.

34" White Fir, alive and standing, bears N 26° W (record) 79.2' (record) blaze but scar visible.

Description of monument and accessories | established to perpetuate the original location of this corner:

From corner location as described above

New bearing tree, 18" Fir bears N 26° E, a distance of 18.5 feet, which I marked T55 R28E S22 BT.

Attached USFS signs, 54-3 and 54-4, to all Bearing Trees, and attached brass tag, marked RLS 1024, to new Bearing Tree. Painted blazes and a 6" wide band fluorescent red around trunks of all trees.

Set 6' steel fence post 5' South of Corner with 54-4 sign.

Thomas F. Upton, Certificate No. R.T.S. 1024

Office of Lo. Sweeney County of Morrow
 State of Oregon hereby certify that the within instrument was filed in this office
 for record on the 12th day of January, 1982
David H. Krumbein by Margaret A. Hughes
 (COUNTY OFFICIAL) (DEPUTY)

FORM R6-7100-57 (9/71)

RECEIVED BY ★ GPO—798-276
Morrow County Surveyor
 Date January 12, 1982
 Rec'd By M. Hughes
 No. 471-K

Ret. during on 11/1/82