

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R-15

History of original corner establishment:

E.W. Sanderson under G.L.O. contract no. 417, dated Aug. 24, 1881, set a basalt stone 15"x 12"x 6", 10" in the ground. Stone marked $\frac{1}{4}$ on N. face. From the corner:
A Pine, 6" dia., N100E, 31 lks.
A Pine, 10" dia., S500W, 18 lks.
Leonard Carter, Public Land Surveyor, under G.L.O. special instructions, Group No. 228, dated Mar. 23, 1938, found the original stone and replaced it with a 1"x 36" iron post with a brass cap marked:
He marked new BTs:
A Lodgepole Pine, 11" dia., N180W, 40 lks.
A Lodgepole Pine, 7" dia., S430E, 19 lks.

DIAGRAM
T5S R28E
 $\frac{1}{4}$ S22
E27

$\frac{1}{4}$ S22
E27
1938

Description of corner evidence found:

I found a 1" iron pipe with a 2 $\frac{1}{2}$ " brass cap (G.L.O.) marked:

$\frac{1}{4}$ S22
E27
1938

From the corner:

A Lodgepole Pine snag, 9" dia., S400E, 12.2 ft.; with scribbling visible.
A stump, 12" dia., N150W, 26.7 ft.; stump is low out, no scribbling.

Description of monument and accessories I established to perpetuate the original location of this corner:

I built a mound of stone around the monument and marked new BTs:

A Western Larch, 13" dia., N61 $\frac{1}{2}$ 0E, 103.4 ft.; marked: $\frac{1}{4}$ S22 BT
A Western Larch, 9" dia., S870E, 98.5 ft.; marked: $\frac{1}{4}$ S27 BT

BTs have blaze and a 6" band painted red, BT tags and "Land Survey Monument" signs. New BTs have alum. "PLS 1832" washers nailed to the bottom of the blaze. There is a 6' steel fence post with a "Land Survey Monument" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 18 $\frac{1}{4}$ 0E.

September 8, 1988

RECEIVED BY
Morrow County Surveyor

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Date 11/1/88

Rec'd BY CHIK

Fayette S. Munro

No. D 874K

OREGON
JULY 13, 1979
FAYETTE S. MUNRO
1832

Office of..... County of.....

State of..... I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

(COUNTY OFFICIAL)

(DEPUTY)