

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V-19

DIAGRAM	
T5S R28E	1/4
S26	S35
S26	S35
1938	

History of original corner establishment:
 Edward W. Sanderson under G.L.O. contract no. 417, 7" dated Aug. 24, 1881, set a basalt stone 14" x 12" x 7" mkd. 1/4 on N. face from which:
 A Pine, 6" dia., S50W, 6 lks.
 A Pine, 9" dia., N50W, 6 lks.

Leonard Carter, Public Land Surveyor, under G.L.O. Special Instructions, Group No. 228, dated Mar. 23, 1938, found a sandstone 14" x 8" x 6" firmly set, mkd. 1/4 on N. face. At the corner point he set an iron post 3' long, 1" dia. with a brass cap mkd. ;
 He marked new BTs:
 A Tamarack, 21" dia., N110W, 86 lks.
 A Douglas Fir, 13" dia., S380E, 82 lks.

Description of corner evidence found:

I found a 1" iron pipe with a 2 1/2" brass cap (GLO) mkd. ;
 From the corner:

1/4 S26
 S35
 1938

A Western Larch, 21" dia., N110W, 56.8 ft. ;
 with healed blaze.
 A Douglas Fir, 20" dia., S380E, 54.1 ft. ;
 with healed blaze.

Description of monument and accessories | established to perpetuate the

original location of this corner:
 I marked new BT:


A Western Larch, 16" dia., N580W, 111.4 ft. ; mkd. : X at breast height and BT at base.

I drove a 6' steel fence post, N46 1/4 E, 4.7 ft. and attached a "Land Survey Monument" sign.

BTs have blaze and a 6" band painted red, BT tags and "Land Survey Monument" signs. New BT has, additionally, an alum. "PLS 1832" washer nailed to the bottom of the blaze.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 190E.

July 27, 1990



Office of..... County of.....
 State of..... I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by..... (DEPUTY)
 (COUNTY OFFICIAL)

Form R6-7100-57 (9/71)

RECEIVED BY
 Morrow County Surveyor

Date 1/9/91
 Rec'd By ADP
 No. 2031-19