

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

A-7

History of original corner establishment:

This corner was not established in the original survey. Corner incorrectly established in 1979 by PLS 1106.

DIAGRAM	
FOUND MONUMENT	
T 4 S	R 29 E
S 32	
1/4	S 5
T 5 S	R 29 E
1979	
PLS 1106	

Description of corner evidence found:

Found 3 inch brass cap, 2 inches above ground set by PLS 1106 in 1979, by proportionate measure along the township line.  
 NOTE: In 1986 survey, 1979 proportion found incorrect and therefore, the found monument is not accepted.

17 inch douglas fir bears S. 36.5° E., 54.4 feet with visible scar.  
 18 inch douglas fir bears S. 25° W., 65.8 feet with visible scar.

NOTE: These trees witness 1979 brass cap not accepted by this survey.

Description of monument and accessories | established to perpetuate the original location of this corner:

At mid-point of north line, Section 5, set 3-1/4 inch PCL aluminum cap on 2-1/2 x 30 inch aluminum pipe 28 inches in the ground. Cap marked:

T 4 S	R 29 E
1/4	S 5
T 5 S	R 29 E
PLS 1058	1986

NOTE: These accessories to monument established in 1986:  
 7 inch fir bears S. 36° W., 43.7 feet marked: X BT  
 13 inch larch bears S. 16° E., 101.0 feet marked: X BT  
 Brass Cap by PLS 1106 bears N. 89° 53' 42" E., 16.34 feet.

Approximately 810 feet West to Road 170

54-3, and 54-9 or 54-4 signs on all bearing trees. Trees have red band and blazes are painted red. Brass washer nailed to BT portion of blaze on new bearing trees and on old bearing trees if needed. Steel guard post with 54-9 or 54-4 sign set 0 to 6 feet from corner. Distance measured in horizontal feet to center of tree. Bearings measured with magnetic compass, 20° East declination.

CERTIFICATION

I, Ken E. Jenkins  
 certify the information shown herein is true and correct.

*Ken E. Jenkins*  
 Registered Professional Land Surveyor  
 T. J. TOMPSON, N. O. 1058  
 State of Oregon, License No. 1058  
 I hereby certify that I am duly licensed and authorized to perform the work herein  
 or that I am duly licensed and authorized to perform the work herein  
*Ken E. Jenkins*  
 Signature of Surveyor & Seal

Date: 7-86 OREGON RULES 1058  
 Employer: THORNTON CONSULTANTS  
TOMPSON

Office of SURVEYOR County of Harney  
 State of Oregon, I hereby certify that the within instrument was filed in this office  
 for record on the day of November, 1986  
David H. Klein by Ken E. Jenkins  
 (COUNTY OFFICIAL) (DEPUTY)