

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

TSS, R29E
A-7

History of original corner establishment:

This corner was not established in the original survey. Corner incorrectly established in 1979 by PLS 1106.

DIAGRAM			
FOUND MONUMENT			
T 4 S	R 29 E		
S 32			
1/4	S 5		
T 5 S	R 29 E		
1979			
PLS 1106			

Description of corner evidence found:

Found 3 inch brass cap, 2 inches above ground set by PLS 1106 in 1979, by proportionate measure along the township line.
NOTE: In 1986 survey, 1979 proportion found incorrect and therefore, the found monument is not accepted.

17 inch douglas fir bears S. 36.5° E. 54.4 feet with visible scar.
18 inch douglas fir bears S. 25° W., 65.8 feet with visible scar.
NOTE: These trees witness 1979 brass cap not accepted by this survey.

Description of monument and accessories established to perpetuate the original location of this corner:

At mid-point of north line, Section 5, set 3-1/4 inch PCL aluminum cap on 2-1/2 x 30 inch aluminum pipe 28 inches in the ground. Cap marked:

T 4 S R 29E
1/4 S 5
T 5 S R 29 E
PLS 1058
1986

NOTE: These accessories to monument established in 1986:
7 inch fir bears S. 36° W., 43.7 feet marked: X BT
13 inch larch bears S. 16° E., 101.0 feet marked: X BT
Brass Cap by PLS 1106 bears N. 89° 53' 42" E., 16.34 feet.

Approximately 810 feet West to Road 170

54-3, and 54-9 or 54-4 signs on all bearing trees. Trees have red band and blazes are painted red. Brass washer nailed to BT portion of blaze on new bearing trees and on old bearing trees if needed. Steel guard post with 54-9 or 54-4 sign set 0 to 6 feet from corner. Distance measured in horizontal feet to center of tree. Bearings measured with magnetic compass, 20° East declination.

CERTIFICATION

I, Ken E. Jenkins
certify the information shown herein is true and correct.

Ken E. Jenkins
Ken E. Jenkins
REGISTERED LAND SURVEYOR
RENE'S TRUST
I, Thomas S. Harrison
REGISTERED LAND SURVEYOR
I hereby certify that the information shown herein is true and correct.
by me or under my direct supervision
work performed

Signature of Surveyor & Seal
Date: 7-86 REGISTERED 1058
Employer: THORNTON CONSULTANTS
1058LS

Office of Surveyor County of Harrison
State of Oregon I hereby certify that the within instrument was filed in this office
for record on the 11th day of November, 1986
David H. Klemm
(COUNTY OFFICIAL) (DEPUTY)