


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

None



Description of corner evidence found:

None

Description of monument and accessories | established to perpetuate the original location of this corner:

At point for corner set 3-1/4 inch PCI aluminum cap on 2-1/2 x 30 inch aluminum pipe 10 inches in ground. 4 feet dia. mound of stone about monument cap marked as shown above.

8 inch white fir bears S. 77° W., 24.1 feet, Marked CN 1/16 S S BT
9 inch larch bears N. 25° E., 30.1 feet marked CN 1/16 S S BT
Center of found 2 feet dia., mound of stone bears N. 24° E., 8.0 feet.

375 feet East to Road 170

54-3, and 54-9 or 54-4 signs on all bearing trees. Trees have red band and blazes are painted red. Brass washer nailed to BT portion of blaze on new bearing trees and on old bearing trees if needed. Steel guard post with 54-9 or 54-4 sign set 0 to 6 feet from corner. Distance measured in horizontal feet to center of tree. Bearings measured with magnetic compass, 20° East declination.


CERTIFICATION

I, Ken E. Jenkins

certify the information shown herein is true and correct.

Signature of Thomas M. Hanson
 Signature Ground Party Chief
 Thomas M. Hanson

certify that this former record correctly represents work performed by me or under my direction



Signature of Surveyor & Seal
 Reg. No. PLS 1058
 PROFESSIONAL CONSULTANTS
 Employer:

Office of Surveyor County of Morrow
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 11th day of November, 1986
Thomas M. Hanson by Ken E. Jenkins
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)