


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

None



Description of corner evidence found:

None

Description of monument and accessories | established to perpetuate the original location of this corner:

- At corner point set 3-1/4 inch PCI aluminum cap on 2-1/2 x 30 inch aluminum pipe 28 inches in the ground. Cap marked as shown above.
- 10 inch Tarch bears N. 20° W., 46.3 feet marked NE 1/16 S S BT
- 6 inch lodgepole pine bears N. 52° W., 28.8 feet marked NE 1/16 S S BT
- ± 400 feet West to Highway 53
- 54-3, and 54-9 or 54-4 signs on all bearing trees. Trees have red band and blazes are painted red. Brass washer nailed to BT portion of blaze on new bearing trees and on old bearing trees if needed. Steel guard post with 54-9 or 54-4 sign set 0 to 6 feet from corner. Distance measured in horizontal feet to center of tree. Bearings measured with magnetic compass, 20° East declination.

CERTIFICATION

I, Ken F. Jenkins

certify the information shown herein is true and correct.

Ken F. Jenkins
 REGISTERED PROFESSIONAL LAND SURVEYOR
 Signature of Record Party Chief
 Thomas M. Hanson
 By *Thomas M. Hanson* or under my direction

Thomas M. Hanson
 Signature of Surveyor & Seal
 THOMAS M. HANSON Date: 7-86 Reg. No. PLS 1058
 103215 Employer
 PROFESSIONAL CONSULTANTS

Office of Surrey County of Morran
 State of Oregon I hereby certify that the within instrument was filed in this office
 for record on the 11 day of November, 1986
David H. Klees
 (COUNTY OFFICIAL) by (DEPUTY)

Form RG-7100-57 (9/71)

DFJ