

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

C-11

History of original corner establishment:

This corner was established in error in a 1979 survey by LS 1106.

This corner certificate corrects the corner monument and supercedes the certificate for 1979.

DIAGRAM
T5S R29E
C1/4 S4
1987
PLS 1106

Description of corner evidence found:

The 1979 monument set in error.

Description of monument and accessories | established to perpetuate the original location of this corner:

Moved 1979 monument to proper position, a move of S30°34'30"W-9.05'. The 1979 monument, a 3" brass cap on a 2 1/2" by 30" galv. iron pipe was set 16" in the ground and surrounded with a mound of earth and stone. Cap marked as shown in corner diagram. The monument is set in true corner position and is not a witness corner.

Used bearing trees marked in 1979 as references:

A 14" western larch bears N22 1/2°E-12.2' scribed C1/4 S4 BT-BT on partially healed double blaze.

A 10" douglas fir bears S16 1/2°W-17.7' scribed C1/4 S4 BT-BT on partially healed double blaze.

Attached sign 54-3 and 54-4 and painted face of blaze and a 6" red band around each bearing tree. Bearing trees have a brass washer stamped PLS 1106 nailed to face of lower blaze. Set steel fence post North of corner and attached sign 54-2 and 54-9.

Compass declination - 19° East.

This corner was established on September 25, 1987.

WILLIAM R. WELLS
MORROW COUNTY SURVEYOR

REGISTERED PROFESSIONAL LAND SURVEYOR
<i>WILL R. WELLS</i>
OREGON JULY 22, 1977 WILLIAM R. WELLS 1105

Date 11/87

Rec'd By OKIK

No. B 862K
MOTION

County of.....Morrow.....County of.....

Office of.....Oregon.....I hereby certify that the within instrument was filed in this office

for record on the 15 day of October, 1987

David A. Kila
(COUNTY OFFICIAL) by (DEPUTY)