


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

None



Description of corner evidence found:

None

Description of monument and accessories | established to perpetuate the original location of this corner:

At position for corner set 3-1/4 inch PCL aluminum cap on 2-1/2 x 30 inch aluminum pipe, 27 inches in the ground. Cap marked as shown above.

8 inch spruce bears S. 77° W., 21.9 feet, marked C 1/4 S 5 BT
10 inch larch bears N. 11° W., 32.9 feet, marked C 1/4 S 5 BT

± 75 feet. West to Highway 53

54-3, and 54-9 or 54-4 signs on all bearing trees. Trees have red band and blazes are painted red. Brass washer nailed to BT portion of blaze on new bearing trees and on old bearing trees if needed. Steel guard post with 54-9 or 54-4 sign set 0 to 6 feet from corner. Distance measured in horizontal feet to center of tree. Bearings measured with magnetic compass, 20° East declination.

CERTIFICATION

I, Ken R. Jenkins

certify the information shown herein is true and correct.

Signature: Ken R. Jenkins
Ground Party Chief

REGISTERED PROFESSIONAL
THOMAS M. HANSON

LAND SURVEYOR
By this seal, I certify that this former record correctly represents work performed in my direction.

Signature of Surveyor & Seal
Thomas M. Hanson

OREGON
JUNE 19, 1966: 7-86
Reg. No. P.L.S. 1058
THOMAS M. HANSON
10581 Employer
PROFESSIONAL CONSULTANTS

Office of: Surveyor County of: Morrow
State of: Oregon I hereby certify that the within instrument was filed in this office
for record on the 10th day of November, 1986
David H. Kline by Ken R. Jenkins
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)