


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index No. E-11

History of original corner establishment:

This corner was originally established by Frank W. Campbell under Contract No. 468 dated April 12, 1883. The original notes state that at the corner a marked pine post 3' long by 3" square was set 24" in the ground for the corner from which:
 An 11" pine bears S50° W 9 lks (5.9 ft) marked $\frac{1}{5}$ BT.
 An 8" fir bears N 12° W 39 Lks (25.7 ft) marked $\frac{1}{5}$ BT.



No record of subsequent remonumentation found in County Records .
 Description of corner evidence found:
 None. Corner established by survey.

Description of monument and accessories established to perpetuate the original location of this corner


At the corner position a 2 inch by 30 inch iron pipe, with brass cap marked as shown, was set 29 inches in the ground.
 Set steel fence post east of corner on section line and attached sign 54-4.
 Established 2 new BT's:
 A 9" tamarack bears N 19° W, 36.2 feet scribed $\frac{1}{4}$ S4 BT.
 A 5 $\frac{1}{2}$ " red fir bears S 8° E, 3.7 feet scribed $\frac{1}{4}$ S9 BT.
 New BT's have a lower blaze scribed BT with a brass washer stamped PLS 1106 nailed flush.
 Attached sign 54-3 and 54-4 and painted a red ring around all BT's.
 Location poster is located on the west side of Road S415 110' ± east of corner.

Used steel tape and magnetic compass with 19 $\frac{1}{2}$ ° east declination. Measured to center of Bts.
 See map of survey.

This corner set August 28, 1979.

Witnesses:
 Greg Flowers LSIT
 B. J. Reynolds

REGISTERED PROFESSIONAL LAND SURVEYOR
<i>William R. Wells</i> OREGON JULY 22, 1977 WILLIAM R. WELLS 1106



Office of County Surveyor County of MORTW
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the day of
 (COUNTY OFFICIAL) by (DEPUTY)

RECEIVED BY

Morrow County Surveyor
 Date Oct 20 1979
 Rec'd By Montana Wheeler
 No. 255-4