


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

5-19

DIAGRAM T6S R25E



History of original corner establishment:  
Corner originally established by E.W. Sanderson  
under Contract No. 368, dated Sept. 7, 1880.

Government field notes state:

Set stone 10x10x8 in stone mound for ¼ Sec. Cor.  
from which.  
A pine 12" in diam., S.10°E. 401ks.

Description of corner evidence found:  
The position of this ¼ corner is determined at record bearing and distance  
from the original BT.

I also found the original corner stone, a basalt stone 10"x8"x8" mkd. ¼ being used  
as a fence weight in wire fence running North and South from original BT. The  
stone was about 10 ft. North of the BT.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Robert D. Baggett*  
OREGON  
JULY 12 1963  
ROBERT D. BAGGETT  
598


See my recorded Map of Survey dated Oct. 1980.

Description of monument and accessories established to perpetuate the  
original location of this corner  
At the Corner point:

Set a 1½"x30" iron pipe 24" in the ground with brass cap marked as shown:

from which, the ORIGINAL BEARING TREE:

A pine, 21" diameter, bears S10°E., 26.4 ft. with partial scribing  
visible in blaze where I opened tree. This tree had completely healed over  
blaze, blaze was 6" inside.



I scribe NEW BEARING TREES:

A fir 7" diam., bears N.69°E., 36.9 ft. mkd. ¼S11 BT.  
A fir 12" diam., bears S.37°W., 5.7 ft. mkd. ¼S14 BT.

Brass Cap Marker

Buried Original corner stone North and alongside pipe and surrounded pipe with  
mound of stone, 3 ft. base, to top of pipe. This corner is 6 ft. west of a North-  
South wire fence.

Used magnetic compass with 17° east variation and steel tape, measuring to face of  
of new BTs blaze.

Done: Oct. 13, 1980  
Witness: G.L. Earl, O.P.L.S. Surveyor County of Morrow  
Office of Oregon, I hereby certify that the within instrument was filed in this office  
State of Oregon, Nov. 1980  
for record on the 18 day of  
*Daniel W. King* by  
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY  
Morrow County Surveyor  
Date 11-10-80  
Rec'd By M.J.J  
No. # 395-K

refer to drawing no. 393-K