

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


J-21

History of original corner establishment:

Corner originally established by E. W. Sanderson under Contract No. 368, dated Sept. 7, 1880.

Government field notes state:

Marked a fir 16" in diam. for cor. to Secs. 13, 14, 11, 12 from which:
A fir 12" in diam., N. 38° E., 28 lks.
A fir 12" in diam., N. 30° W., 31 lks.
A pine 30" in diam., S. 60° W., 26 lks.



Description of corner evidence found:

I found the remains of the original corner tree which is now a badly deteriorated fir root wad.
From which the ORIGINAL BEARING TREES:

The remains of a fir stump bears N. 35° E., 19.1 ft. (stump worn to ground level)
The remains of a fir stump bears N. 30° W., 21.4 ft. (stump worn to ground level)
The remains of a pine stump (3 ft. high), bears S. 63° W., 18.7 ft. with blazed chip marked BT. (This chip had been removed from stump, I nailed it back on the stump).


See my recorded Map of Survey dated Oct. 1980.

Description of monument and accessories I established to perpetuate the original location of this corner

At the corner point:

Set a 1 1/2"x30" iron pipe 24" in the ground with brass cap marked as shown: From which I scribe NEW BEARING TREES:

- A red fir, 19" in diam. bears N. 43° E., 78.4 ft. mkd. T6SR25E S12 BT.
- A red fir, 23" in diam. bears S. 1° E., 61.2 ft. mkd. T6SR25E S13 BT.
- A red fir, 15" in diam. bears S. 40° W., 139.1 ft. mkd. T6SR25E S14 BT.
- A red fir, 16" in diam. bears N. 73° W., 98.7 ft. mkd. T6SR25E S11 BT.



Surrounded pipe with mound of stone 3 ft. base to top of pipe.

Used magnetic compass with 19° East variation and steel tape, measuring to face of BT blaze.

Done: Oct. 15, 1980.

Witnesses: G. L. Earl. O.P.L.S. and R. L. Graham, Kinzua corp.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. Baggett
 OREGON
 JULY 12, 1963
 ROBERT D. BAGGETT
 598

Office of Surveyor County of Morrow
 State of Oregon I hereby certify that the within instrument was filed in this office
 for record on the 15th day of November, 1980.
David H. Walker
 (COUNTY OFFICIAL) by (DEPUTY)

RECEIVED BY

Morrow County Surveyor
 Date 11-10-80
 Rec'd By M. J. J.
 No. # 397-K

ref. to survey no. # 398-K