


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

K-21

History of original corner establishment:  
North 1/16 corner between sections 13 and 14,  
T6S., R25E., W.M., not previously established of  
record.



Description of corner evidence found:  
None.

I establish, by Survey, the North 1/16 corner between Sections 13 & 14 on the Section line at midpoint between the NE corner of Sec. 14 and the E 1/4 corner of Sec. 14.

See my recorded Map of Survey dated Oct. 1980.

Description of monument and accessories I established to perpetuate the original location of this corner  
At the corner point:

Set a 1 1/2"x30' iron pipe 20" in the ground with brass cap marked as shown.

From which I scribe NEW BEARING TREES:  
A White Fir 14" diam., bears S. 30° E., 13.9 ft., mkd. N1/16 S13 BT.  
A White Fir 11" diam., bears S 68° W., 20.8 ft. mkd. N1/16 S14 BT.  
Surrounded pipe with mound of stone, 3 ft. base, to top of pipe.

Used true bearings (Solar Observation) and steel tape measuring to face of BT blaze.

Done: Oct. 16, 1980.

Witness: G. L. Earl, O.P.L.S. & Sid Zinter Jr., Land Owner

T6SR25E  
N1/16  
S14 | S13  
1980  
OPLS 598

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
JULY 12, 1963  
ROBERT D. BAGETT  
598

Office of Surveyor ..... County of Morrow  
State of Oregon .....  
I hereby certify that the within instrument was filed in this office  
for record on the 10 day of .....  
Nov. 1980  
by .....  
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Morrow County Surveyor  
Date 11-10-80

Rec'd By M.A.J.  
No. # 401-K