


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

2-17

DIAGRAM T6S R25E



History of original corner establishment:  
Corner originally established by E.W. Sanderson  
under Contract No. 368, dated Sept. 7, 1880.

Government field notes state:

Mark a pine 8" diam. for  $\frac{1}{4}$  sec. cor.  
from which:

A pine 6" in diam N.80°E., 71ks.  
A pine 6" in diam West 71ks.

Description of corner evidence found:  
I found the remains of the original corner tree roots and an 18" long by 4" wide  
piece of pine blazed and scribed  $\frac{1}{4}$   
from which:

The ORIGINAL BEARING TREES:

The stumphole of the remains of a pine bears N80°E., 4.6 ft. part of pine is  
blazed and marked  $\frac{1}{8}$ S BT.

The remains of a deteriorating pine bears West 6.0 ft., part of pine is blazed  
and marked  $\frac{1}{8}$ S BT.

See my recorded Map of Survey dated Oct. 1980.

Description of monument and accessories I established to perpetuate the  
original location of this corner.  
At the corner point:

Set a  $1\frac{1}{2}$ "x30" iron pipe, 20" in the ground with brass cap marked as shown:

from which I scribe NEW BEARING TREES:

A pine 14" diam., bears S.48°E., 49.3 ft. mkd  $\frac{1}{2}$ S14 BT.  
A pine 9" diam., bears S.11°W., 40.0 ft. mkd  $\frac{1}{2}$ S15 BT.


Surrounded pipe with mound of stone, 3 ft. base to top of pipe.

Used magnetic compass with 17° east variation and steel tape, measuring  
to face of BT blaze.

This corner is S.58°W. 28 ft. from Rock Crib at corner of fences running  
North and East.

Done: Oct. 9, 1980

Witness: G.L. Earl, O.P.L.S.



Brass Cap Marker

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Robert D. Baggett*  
OREGON  
JULY 12, 1963  
ROBERT D. BAGGETT  
598

Office of SURVEYOR ..... County of MORTOW .....  
State of Oregon ..... I hereby certify that the within instrument was filed in this office  
for record on the 10 day of NOV. 1980  
*David H. Wilson*  
(COUNTY OFFICIAL) by ..... (DEPUTY)

RECEIVED BY

Mortow County Surveyor  
Date 11-10-80  
Rec'd By M.D.J.  
No. # 404-K

refer to survey no. # 393-K