


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

L-23

DIAGRAM T6S R25E



History of original corner establishment:

Center ¼ corner Sec. 13, T6S R25 E., W.M. not previously established of record.

Description of corner evidence found:

None.

I establish, by survey, the center ¼ corner of Sec. 13 at the intersection of lines from opposite corresponding ¼ corners.

See my recorded Map of Survey dated Oct. 1980.

Description of monument and accessories I established to perpetuate the original location of this corner

At the corner point:

Set a 1½"x30" iron pipe, 24" in the ground with brass cap marked as shown.

From which I scribe NEW BEARING TREES:

A red fir, 11" in diam., bears S. 73° W., 41.1 ft., mkd. C¼ S13 BT.
A pine, 13" in diam., bears S., 37° W., 36.6 ft., mkd. C¼ S13 BT.


Surrounded pipe with a mound of stone.

Used magnetic compass with 18° East variation and steel tape, measuring to face of BT blaze.

Done Oct. 23, 1980.

Witness: G. L. Earl, O.P.L.S. and R. L. Graham, Kinzua corp.

BRASS CAP
MARKED.



REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. Baggett
 OREGON
 JULY 12, 1963
 ROBERT D. BAGETT
 598

Office of.....SURVEYOR..... County of.....MORROW.....
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the 19th day of November, 1980.
David H. Klevin
 (COUNTY OFFICIAL) by (DEPUTY)

RECEIVED BY

Morrow County Surveyor

Date 11-10-80

Rec'd by M.D.I.

No. # 511-K

Refer to survey no. # 395-K