


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

P-17

DIAGRAM T6S 25E



History of original corner establishment

Corner originally established by E. W. Sanderson under Contract No. 368, dated Sept. 7, 1880.

Government field notes state:

Set Stone 16x14x10 for 1/4 Sec. Cor. from which a Tamarack 30 in. diam., S. 80° E., 29 lks. Tamarack 24 in diam., S. 80° W., 39 lks.

Description of corner evidence found:

The position of this corner is determined at record bearing and distance from one remaining original BT.

I also found the original corner stone, a basalt stone 16x14x10" dimly marked 1/4 in a hole beside a fence corner, about 4 ft NE of corner position.

I found no evidence of the other original BT, it has probably been destroyed in logging or fencing operations.

See my recorded Map of Survey, dated Oct. 1980.

Description of monument and accessories I established to perpetuate the original location of this corner

At the corner point:

Set a 1 1/2"x30" iron pipe 27" in the ground with brass cap marked as shown:

From which:

The Original BEARING TREE:

A Tamarack stump, 23" diam., bears S. 80° W., 25.7 ft. mkd 1/4.

I scribened BEARING TREES:

A Tamarack 23" diam., bears N. 29° E., 28.6 ft. mkd. 1/4 S23 BT.


A Fir 10" diam., bears N. 84° W., 40.0 ft. mkd. 1/4 S22 BT.

Buried original corner stone North and along side iron pipe. Used magnetic compass with 17° East variation and steel tape measuring to face of BT blaze.

Done: Oct. 7, 1980

Witness: G. L. Earl, O.P.L.S.

Brass Cap
Marked



REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. Baggett
OREGON
JULY 12, 1963
ROBERT D. BAGGETT
598

Office of Surveyor County of MORTWOW
State of Oregon
I hereby certify that the within instrument was filed in this office
for record on the 19 day of Nov. 1980
David H. ...
(COUNTY OFFICIAL) by (DEPUTY)

RECEIVED BY

Morrow County Surveyor
Date 11-10-80
Rec'd By W. J. I.
No. # 403-K
refer to survey no. #393-K