

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

C - 1
DIAGRAM



History of original corner establishment:

The original corner was established by Edward W. Sanderson on November 4, 1880, under GLO contract No. 368, as follows:

Set a stone, 12" x 10" x 7", in a stone mound for 1/4 section corner, from which:

- A 30" pine bears S70° W, 18 links (11.88 feet).
- A 9" pine bears S35° W, 18 links (11.88 feet).

Original corner evidence recovered:

Found the original corner stone solidly set in a mound of stones. The corner stone is 17" x 12" x 5" and is faintly, but plainly marked "1/4" on the east face, from which:

- A high cut 23" Ponderosa Pine stump with a healed blaze facing the corner stone and an open blaze with fragmentary scribes visible facing north, bears S70° W, 11.9 feet to the blazed face.
- A 12" sawn Ponderosa Pine stump, no marks remaining, bears S34° W, 11.9 feet to the assumed location of the blazed face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 25" into the ground. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone along the east side of the pipe and build a mound of stones around the pipe, from which:

- A 10" Ponderosa Pine, scribed "1/4 S6 B1", bears N74° 30' E, 22.7 feet.
 - A 7" Ponderosa Pine, scribed "1/4 S6 BT", bears S53° 30' E, 65.9 feet.
 - A 7" Ponderosa Pine, scribed "R25E BT", bears S25° W, 7.7 feet.
 - A 7" Ponderosa Pine, scribed "T6S BT", bears N89° W, 30.3 feet.
- The new bearing trees are scribed on double blazes and have a 3/4" brass washer, marked "PLS 1636", nailed flush to the bottom of the lower blaze.

I hereby certify this corner point was perpetuated as hereon described on May 7, 2003. Magnetic declination set in compass: 17° E. NAD 83 UTM Zone 11 position: 4994748N 290086E (plus or minus two meters).



RECEIVED BY
Morrow County Surveyor

Date: 1-4-2014
 Recd By: S.K.H.
 No.: 6S26C1
 Folder No.: _____

Renews June 30, 2003