


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. E-17

History of original corner establishment:

The original corner was established by Ed Sanderson under G.L.O. contract 368, dated September 7, 1880. His record reads:



Set Stone 14x14x8 for cor. to secs. 10-11-2 & 3 from which
 a pine 15 in dia bears N70°E, 64 lks- dist
 " " 24 " " S. 58°E 83 " "
 " " 24 " " S57°W 45 " "
 " " 28 " " N.40°W. 77 " "

Description of corner evidence found:
 Found stone 14x14x7. Fragments in hole indicate back 1" had spalled off. No marks visible on stone.

Found Ponderosa Pine stump with scribed BT fragment lying in rotted wood at base which bears N69°00'E, 42.1'. Found Ponderosa Pine stump which bears S58°00'E, 54.7'. Found Ponderosa Pine stump which bears N38°30'W, 50.8'. Found Ponderosa Pine stump which bears S47°15'W, 29.7'. This last stump was at the top of the road cut and possibly was moved during the construction of the road.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set a 2" I.D. galvanized iron pipe 30" long with 2 1/2" brass cap 26" into the ground and stamped the cap as shown in diagram above. Buried the original stone along side the monument.

Placed a 3' diameter collar of stone around the monument and set a steel fence post 5' west of the monument with Forest Service Land Survey Monument sign attached.

Scribed T6S R26E S2 BT on a 10" Ponderosa Pine which bears N51°15'E, 105.3'. Scribed T6S R26E S3 BT on a 17" Ponderosa Pine which bears N36°00'W, 44.2'. Scribed T6S R26E S10 BT on a 14" Ponderosa Pine which bears S32°15'W, 46.6'. Scribed T6S R26E S11 BT on a 11" Ponderosa Pine which bears S67°30'E, 80.2'. Each scribe is in a 36" blaze. The bearings are based on the record bearing of S58°E. Nailed an aluminum washer, stamped RLS 852, between the letters B and T on each new bearing tree. Painted a 6" red band around both old and new bearing trees and attached Forest Service Land Survey Monument and Bearing Tree signs.

I certify the above corner point was perpetuated as hereon described on September 18, 1987.

REGISTERED PROFESSIONAL LAND SURVEYOR

OREGON JULY 12, 1968 DAVID L. HADDOCK 852

Office of COQUITY SURVEYOR County of MORROW
 State of OREGON, I hereby certify that the within instrument was filed in this office
 for record on the 18 day of DECEMBER, 1987
DLE by David L. Haddock
 (COUNTY OFFICIAL) (DEPUTY)