


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. G-22

History of original corner establishment:

This corner not previously established.



Description of corner evidence found:

K tag indicates center west 1/16 in general area.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set a 2" I.D. galvanized iron pipe 30" long with 2 1/2" brass cap 26" into the ground and stamped the cap as shown in diagram above.

Placed a 3' diameter collar of stone around the monument and set a steel fence post 5' north of the monument with Forest Service Land Survey Monument and Property Boundary signs attached.

Scribed CW1/16 S12 BT on a 9" Douglas Fir which bears N81°05'E, 20.8'. Scribed CW1/16 S12 BT on a 10" Douglas Fir which bears S30°22'E, 35.5'. Each scribe is in a 24" blaze. The bearings are true. Nailed an aluminum washer, stamped RLS 852, between the letters B and T on each new bearing tree. Painted a 6" red band around new bearing trees and attached Forest Service Land Survey Monument and Bearing Tree signs.

I certify the above corner point was established as hereon described on September 18, 1987.

REGISTERED PROFESSIONAL LAND SURVEYOR

David L. Haddock

OREGON JULY 12, 1968 DAVID L. HADDOCK 352

Office of COUNTY SURVEYOR County of MORRISON State of OREGON I hereby certify that the within instrument was filed in this office for record on the 18 day of DECEMBER, 1986 by (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)