

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. G-23

History of original corner establishment:  
This corner not previously established.

DIAGRAM	
T6S R26E	
1	
C---S12	
4	
PLS 852	
1987	

Description of corner evidence found:  
K tag indicates center 1/4 in general area.

Description of monument and accessories | established to perpetuate the original location of this corner:  
Set a 2" I.D. galvanized iron pipe 30" long with 2 1/2" brass cap 26" into the ground and stamped the cap as shown in diagram above.  
Placed a 3' diameter collar of stone around the monument and set a steel fence post 5' west of the monument with Forest Service Land Survey Monument sign attached.

Scribed C1/4 S12 BT on a 10" Ponderosa Pine which bears N19°54'E, 44.2'. Scribed C1/4S12 BT on a 15" Juniper which bears N81°05'W, 143.7'. Each scribe is in a 24" blaze. The bearings are true.  
Nailed an aluminum washer, stamped RLS 852, between the letters B and T on each new bearing tree. Painted a 6" red band around new bearing trees and attached Forest Service Land Survey Monument and Bearing Tree signs.

I certify the above corner point was established as hereon described on September 18, 1987.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*David L. Haddock*

OREGON  
JULY 12, 1988  
DAVID L. HADDOCK  
852

Office of CLATSOP COUNTY SURVEYOR County of MCRAE  
State of OREGON I hereby certify that the within instrument was filed in this office  
for record on the 19 day of DECEMBER, 1986  
by DD (COUNTY OFFICIAL) (DEPUTY)