


History of original corner establishment:

The original corner was established by Ed Sanderson under G.L.O. contract 368, dated September 7, 1880. His record reads:

Set stone 12x12x10, in stone mound for cor. to secs. 12 & 13 T.6S. R26E-



Description of corner evidence found:
Found stone 12x12x10 with 6 notches on the north face and 5 notches on the south face in a small stone mound.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set a 2" I.D. galvanized iron pipe 30" long with 2 1/2" brass cap 26" into the ground and stamped the cap as shown in diagram above. Buried the original stone along side the monument.

Placed a 3' diameter collar of stone around the monument and set a steel fence post 5' west of the monument with Forest Service Land Survey Monument sign attached.

Scribed T6S R26E S12 BT on a 12" ponderosa pine which bears N33° 47'W, 202.2'. Scribed T6S R26E S13 BT on a 7" Juniper which bears S41° 41'W, 124.4'. Scribed T6S R27E S18 BT on a 12" ponderosa pine which bears S30° 40'E, 122.3'. Scribed T6S R27E S7 BT on a 9" Juniper which bears N37° 05'E, 184.5'. Each scribe is in a 36" blaze. The bearings are true. Nailed an aluminum washer, stamped RLS 852, between the letters B and T on each new bearing tree. Painted a 6" red band around new bearing trees and attached Forest Service Land Survey Monument and Bearing Tree signs.

I certify the above corner point was perpetuated as hereon described on September 18, 1987.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David L. Haddock

OREGON
JULY 12, 1968
DAVID L. HADDOCK
852

Office of COQUITY SURVEYOR County of MORRISON
State of OREGON, I hereby certify that the within instrument was filed in this office
for record on the 13 day of DECEMBER, 1986
DAVID L. HADDOCK by _____ (DEPUTY)
(COUNTY OFFICIAL)