


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J - 5
DIAGRAM



History of original corner establishment:

The original corner was established by Edward W. Sanderson on April 20, 1881, under GLO contract No. 368, as follows:

Set a stone, 20" x 6" x 6", in a mound of stones for the corner to sections 7, 8, 17 and 18, from which:

- A 10" pine bears N38° W, 15 links (9.90 feet).
- A 12" pine bears N60° E, 68 links (44.88 feet).
- A 24" pine bears S35° E, 37 links (24.42 feet).
- A 15" pine bears S40° W, 21 links (13.86 feet).

Original corner evidence recovered:

- I find the original corner stone solidly set in a mound of stones. The corner stone is 14" x 13" x 8" and is marked with two grooves on the north face, from which:
 - A 24" sawn Ponderosa Pine stump with no visible marks remaining, bears N60° E, 43.7 feet.
 - A 36" sawn Ponderosa Pine stump with scribes, "BT", visible, bears S21° E, 22.6 feet.
- The two original bearing trees to the west are uprooted and lying next to the corner stone. Both are fully scribed on double blazes, but I cannot tell where these two trees once stood.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 25" into the ground. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone along the southeast side of the pipe and build a mound of stones around the pipe, from which:

- A 11" Ponderosa Pine, scribed "T6S R26E S8 BT", bears N47° E, 28.9 feet.
 - A 13" Ponderosa Pine, scribed "T6S R26E S17 BT", bears S51° 30' E, 53.7 feet.
 - A 14" Ponderosa Pine, scribed "T6S R26E S18 BT", bears S28° W, 50.8 feet.
 - A 10" Ponderosa Pine, scribed "T6S R26E S7 BT", bears N78° 30' W, 50.5 feet.
- A fence corner, with wire fences projecting south and west, bears S86° W, 41.5 feet.

The new bearing trees are scribed on double blazes and have a 3/4" brass washer, marked "PLS 1636", nailed flush to the bottom of the lower blaze.

I hereby certify the above corner point was perpetuated as hereon described on June 12, 2003. Magnetic declination set in compass: 17° E.
NAD '83 UTM Zone 11 position: 4992287N, 291505E (plus or minus two meters).

RECEIVED BY
Morrow County Surveyor

Dennis L. Gaylord



OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636
Renews June 30, 2005

Date: 1-4-14
Rec'd By: S.K.H.
No.: 6526 JS
Folder No.: _____