

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Refer to: Plat of Stahl 1990 Cadastral Survey
Sections 4 and 8, T.6S., R.27E., W.M.

G-9

History of original corner establishment:
Edward W. Sanderson under G.L.O. contract no. 368,
dated Sep. 7, 1880, set a stone 12"x 10"x 9" in
a stone mound.

DIAGRAM
T6S R27E
1/4
S81S9

Description of corner evidence found:
I found a mound of stone, stone 13"x 9"x 8" lying loose approx. 20'
down slope easterly from mound. Stone was marked 1/4.

Description of monument and accessories I established to perpetuate the original location of this corner:
At the corner point established at center of found mound of stone
I set a 2 1/2"x 30" alum. pipe with a 2 1/2" alum. cap mkd.: T6S R27E
Monument is 14" in the ground and surrounded by a 1/4
mound of stone. Buried original stone alongside. S81S9
PLS 1832
1990

From the corner:
A Douglas Fir, 17" dia., N34 3/40E, 139.8 ft.;
mkd.: 1/4 S9 BT
A Ponderosa Pine, 13" dia., S16 1/40E, 39.2 ft.; mkd.: 1/4 S9 BT
A Ponderosa Pine, 24" dia., S870W, 40.0 ft.; mkd.: 1/4 S8 BT
A Ponderosa Pine, 24" dia., N280W, 91.7 ft.; mkd.: 1/4 S8 BT
BTs have blaze and a 6" band painted red. BT tags, "Land Survey
Monument" signs and alum. "PLS 1832" washers nailed to the bottom of the
blaze. There is a 6' steel fence post with a "Land Survey Monument"
sign within 5' of the corner.
Measured to center of BTs using steel tape and staff compass. Magnetic
declination set at 190E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Fayette S. Munro
OREGON
JULY 13, 1878
FAYETTES S. MUNRO
1832

Sep. 15, 1990

Office of..... County of.....
State of..... I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

RECEIVED BY
(COUNTY OFFICIAL) by (DEPUTY)

Form R6-7100-57 (9/71)

Morrow County Surveyor

Date

Rec'd By

No. R-904 G-9