

History of original corner establishment:  
Edward W. Sanderson subdivided T.6S., R.27E. under  
G.L.O. contract no. 358, dated Sep. 7, 1880. He set  
a stone, 14"x 12"x 7" in a stone mound from which:  
A Pine, 28" dia.; N62°W, 45 lks.  
A Pine, 16" dia.; N48°E, 42 lks.  
A Pine, 20" dia.; S64°E, 117 lks.

(Continued on Page 2 of 2.)

<b>DIAGRAM</b>	
T6S R27E	
58   59	
517   516	

**Description of corner evidence found:**

I found a 2½" alum. pipe with a 3½" alum. cap (BLM) mkd.:	T6S R27E
From which:	58   59
	517   516
	1982


A Ponderosa Pine, 11" dia.; N31°E, 70.9 ft.; scribing visible.  
A Ponderosa Pine, 3¾" dia.; S46°E, 77.2 ft.; scribing visible.  
A Ponderosa Pine, 13" dia.; S35¼°W, 37.7 ft.; scribing visible.  
A Ponderosa Pine, 42" dia.; N62°W, 29.7 ft.;  
tree is dying; scribing visible.

**Description of monument and accessories I established to perpetuate the original location of this corner:**  
I marked a new BT:

A Ponderosa Pine, 14" dia.; N77°W, 103.2 ft.; mkd.; T6S R27E S8 BT  
BTs have blaze and a 6" band painted red, BT tags and "Land Survey Monument" signs. New BT has, additionally, an alum. "PLS 1832" washer nailed to the bottom of the blaze. There is a 6' steel fence post with a "Land Survey Monument" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 20°E.

Aug. 29, 1990



Office of..... County of.....  
State of..... I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....

..... by ..... (DEPUTY)  
(COUNTY OFFICIAL)

RECEIVED BY

Morrow County Surveyor  
Form R6-7100-57 (9/71)

GPO-788-576

Date 11/91  
Rec'd By [Signature]  
No. C-904 T-9

(1 of 2)