

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

A-17

DIAGRAM

T6S R26E
S3|S2
T7S R26E

History of original corner establishment:

Aaron F. York, under G.L.O. contract number 309, dated Nov. 18, 1878, surveyed the north line of T.7S.; R.26E.. He set a stone 20"X 14"X 8" and raised a stone mound at the corner.

Edward W. Sanderson, under G.L.O. contract number 368, dated Sep. 7, 1880, retraced York's line. He found a stone 14"X 10"X 6" in a stone mound from which:

A Pine, 24" dia., N20°W, 89 lks.

Sanderson found this corner 4.00 chs. north of York's record position.

Description of corner evidence found:

None.

Description of monument and accessories | established to perpetuate the original location of this corner:

At proportionate distance (using the Manual's procedure for irregular township boundaries) I set a 2½" X 30" alum. pipe with a 3" alum. cap containing a magnet and marked:

T6S R26E
S3|S2
T7S R26E
PLS 1832
1985-

I built a stone mound around the monument.

From the corner:

A Ponderosa pine, 14" dia., S24°E, 21.8 ft.; marked: T7S R26E S2 BT
A Ponderosa pine, 12" dia., S63½°W, 9.0 ft.; marked: T7S R26E S3 BT

BTs have blaze and a 6" stripe painted red, a BT tag, an "Attention" sign and an alum. "PLS 1832" washer nailed to the bottom of the blaze. There is a 6' steel fence post with an "Attention" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 20½°E..

October 11, 1985.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Fayette S Munro
OREGON
JUL 13, 1979
FAYETTE S MUNRO
1832

Office of..... *SURVEYOR* County of..... *MORROW*
State of..... *OREGON* I hereby certify that the within instrument was filed in this office
for record on the *7th* day of..... *December*....., 1985
..... *David A. Klein* by
(COUNTY OFFICIAL) (DEPUTY)