

SOUTH ONE QUARTER CORNER OF SECTION 21, T 2 S. R. 26 E.

Found the southeast corner of Section 21 in place and identified it by a rock marked with the notches and the letters C. S. as described by Loy Turner as of his survey of May 5, 1914.

Ran ~~West~~ a random line West and set temporary corner at 40.09 chains but found no evidence of corner. The field notes call for a charred stake and pits but as this has been cultivated I did not believe it necessary to make an exhaustive search.

Continue West on random line and at 60.18 ch set temporary corner but could find no evidence of the original corner as this spot is also on cultivated ground.

Went to the Northwest corner of said section but could find no evidence of the corner except that two old fence lines, if produced, would intersect at the approximate location of the corner as shown by the railroad maps. Having no other evidence I use this intersection and run South at 40 chains intersect what was apparently an old road or lane, no evidence of corner. continue south and at 60.00 chains intersect ~~the~~ the produced line of an old fence line across Willow Creek. Continue South and at ~~60.00~~ 79.68 chains intersect the east and west random line at a point 0.40 chains east of the temporary corner. As this line conforms with the old fence lines I accept it as having started from the proper spot and correct back on the east-west random line and place the one quarter corner 6 links south of the temporary corner and mark the corner with a rock 14 X 8 X 4 inches with the mark L/4 and the letters C S 43 set 14 inches below the ground and set a witness corner 160 links East of the true corner. This witness corner is marked by a Rock set in the ground marked with the letters W. C.

Feb 14, 1943

W. Turner
C. S. 43