

The line tree found approximately 1 chain West of the section corner for Sections 34 and 35 was called for on both surveys. I used this line tree as the control for the westerly terminus of my work along the township line.

After tying all of the found evidence along the township line I chose to monument the found mound of stone at the section corner for Sections 1 and 2. This mound of stone included a stone of the approximate size called for in the original notes, however, no marks could be found. An unrecorded bearing tree was found to the Southwest. This tree has in excess of 70 years of overgrowth. It was obvious that this position has been the accepted corner for several years as evidenced by the fenceline and the location markers found. The section corner for Sections 35 and 36 was also remonumented from a mound of stone. As with the section corner for Sections 1 and 2 evidence of prior acceptance of the corner was very apparent. A dead and down and burnt P. Pine fits quite well for the record Southeast bearing tree, however, no scribe marks could be found.

At the 1/4 corner for Section 36 only I remonumented the corner. The found stone was slightly larger than called for in the original notes. I found a P. Pine 9" dia. marked with 1/4 in an open face, which is not of record (see plat). This corner, like those two previously discussed bore evidence of apparent acceptance by previous visitors over the course of several years.

The 1/4 corner for Section 1 and the 1/4 corner for Section 2 were set via proportionate measurement.

The township line was marked as the property boundary of the National Forest lands with 6 foot steel fence posts with Property Boundary signs.

Bearing was based on a solar observation.

Surveyed By: T. Flatebo & Associates, Inc.
P.O. Box 900
Jacksonville, OR 97530

Date: Survey began - November 5, 1980
Completed - April 26, 1981

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Kurt C. Weaver
OREGON
JULY 14, 1978
KURT C. WEAVER
1679