



NARRATIVE: This survey is based on a survey by me in April 1981 for Carney et al in which I subdivided Sec 36 using information from a 1977 Krumbein Survey for Woolsey. In that 1981 survey I computed the correct location of the S.W. cor. Sec. 36 which was 10.2' too far south in Krumbein's survey. I used the computed location of a B.C. at the N.W. cor. of sec. 36 which Krumbein has since moved 46'± easterly to the location of a concrete monument set in 1906 by Worthington in a survey in sec 25. The moving of that NW. cor. only affects my 1981 Carney survey very slightly because the N¼ cor, S¼ cor, & all corners east did not change and Carney's survey is in the NE¼ of Sec. 36. I did not change my 1981 Carney survey.

J. Dennis Edwards

J. Dennis Edwards

SURVEY for DAN GREGORY
 in NE¼ sec 36, T5N, R26E, W.M.
 MORROW COUNTY, OREGON.
 7/6/82 Job # 58103055-B
 (000) of record 0 ½" Iron Rods set
EDWARDS SURVEYING
 567-3336 P.O. Box 763
 HERMISTON, OREGON

November 22, 1982
 M. Hughes
 A-518-K-57

Scale: 1" = 200'