

OFFICIAL SURVEY FOR

ADOLF SKOBO

Establishment of the South boundary of the North west one quarter of the Northeast one quarter of Section 15, T 4 N; R 25 E. W. M.

Petition having been recieved from Adolf Skobo to establish the above described boundary I notified the parties concerned by personal service that on August first, 1930 at 10 o'clock A. M. I would officialy survey and establish the said boundary.

On August 1, 1930 I took to my assistance Percy Bleakman and Lavon Hiatt, who were duly sworn to perform their duties and proceeded with the survey.

I took for a starting point the West one quarter corner of said Section 15, which I found marked with a 4" x 4" post set below the surface of the road, from there @ run;

East (Mag. Var. $21^{\circ}40'$) 2640.0 ft. set point for center of section

5280.0 ft. found $1/4$ corner marked by 4" x 4" post.

From East $1/4$ corner I run

N $0^{\circ}15'E$ 1322.9 ft set point for $1/16$ cor

2645.8 ft. found ^{NE} section corner marked by remains of 4" x 4" post.

From said NE section corner I run

N $89^{\circ}44'W$ 2681 ft. found North $1/4$ corner marked by 4" x 4" post.

From North $1/4$ corner I run

S $0^{\circ}39'E$ 1324.8 ft set hub for SW cor of NW $1/4$ NE $1/4$

2649.7 ft to point set for center of section.

I return to SW cor NW $1/4$ NE $1/4$ and from there I run;

S $89^{\circ}57'E$ 1330.2 Set hub for SE cor of NW $1/4$ NE $1/4$

2660.4 point set for SE cor NW $1/4$ NE $1/4$

You have thirty days to file an appeal

H. Tamplin C. Surge

Folder 99, Date 1/25/1930
 Book: 2, Page: 25A