

SURVEY FOR VETERANS STATE AID COMMISSION

Began at the one quarter corner common to Sections 13 and 14, Tp. 2 s. Rn. 24 E. W. M. which I identified by a stone marked 1/4 as described in the field notes.

From thence I run N. 89°30'W. and at 20.00 chains set temporary corner for the SE corner of the SW $\frac{1}{4}$ NE $\frac{1}{4}$; at 40.00 chains set temporary corner for center of Section 14; at 79.32 chains I intersect the North South fence line at an old fence corner. I search but find no evidence of corner. From the old fence corner I run North along the fence line and intersect an East-West fence line at 40.10 chains. Returned to the old fence corner and ran South along the fence line and at 40.00 chains found a mound of rock that Mr. Snider stated had been pointed out to him as the corner for Sections 14-15-22-23. I accept this as the corner and as the old fence corner checks in so closely I accept it as the 1/4 corner.

As this makes the distance across the section East and West, 79.32 chains I proportion the distance and set the center of the section at 39.66 chains and the SE corner of the SW $\frac{1}{4}$ NE $\frac{1}{4}$ at 19.82 chains from the East 1/4 corner.

From the SE corner of the SW $\frac{1}{4}$ NE $\frac{1}{4}$ I run North, 20.00 chains and set stake for the NW corner of the SW $\frac{1}{4}$ NE $\frac{1}{4}$. This corner lies 49 links North and 39 links West of the corner marked by an iron pin and a stone. (I can find no record of this survey in the office) Thence N 89°30'W; 19.82 chains; thence South 20.00 chains to the center of the section; thence N 89°30'W 39.66 chains to the accepted 1/4 corner; thence South, 40.00 chains; thence S 89°49'E, 19.87 chains as called for in the field notes; thence North, 20.00 chains; thence S 89°48'E, 39.66 chains; ~~thence~~ North, 20.00 chains to the place of beginning.

Survey made May 16, 1943.

Bearings taken with solar compass

H. Tamblin
County Surveyor.

B-46-K