



**NARRATIVE**

This survey changes one done in 1977 by myself for Haws. In that survey I used Government brass caps at the East and West 1/4 corners of Section 23. In a subsequent survey for Nelson in the same area I discovered that when using the brass caps the North-South property lines lied east of old established fence and tree lines. I then searched for more monuments and found one at the intersection of W. 7th & Montana. I used that monument to establish the North-South property lines which fit well with apparent property lines.

In a 1978 survey Walt Cramer found more monuments to back my conclusion that the government monuments are in error.

Also in a 1979 survey and report by McCullough for the Corps of Engineers he recommends that the North-South section lines of Section 23 be resurveyed because the government brass caps do not fit "existing fences and other evidence of occupation".

REGISTERED PROFESSIONAL LAND SURVEYOR  
*G. Dennis Edwards*  
 OREGON JULY 16, 1971  
 G. DENNIS EDWARDS  
 951

RECEIVED BY  
 Morrow County Surveyor  
 Date 7-2-80  
 rec'd by MJJ  
 #375-K-125  
 4th ST.  
 FD. BOLT OVER I.R. BY CRAMER

SURVEY FOR: PAUL HAWS	
LOCATION: E. 1/2, SEC. 23, T5N, R26E., W.M. (BLK 35 W) MORROW COUNTY, OREGON	
DATE: 4-9-80	SCALE: 1"=100'
● MONUMENTS FOUND	(000) OF RECORD
○ 1/2" IRON RODS SET	JOB N° S7710337-A
EDWARDS SURVEYING 567-3336	P.O. BOX 763 HERMISTON, OREGON