



FND. 24" X 10" X 3" STONE
 IN FENCE LINE
 CALL TO GULCH TO
 NORTH 15429 FT IN
 1872 USGLOS NOTES.
 WE MEAS. 426 FT.
 STONE HAD 2 NOTCHES
 ON So. FACE & 4 NOTCHES
 ON EAST FACE.

FENCE COR.
 ROCK CRIB
 SE COR SEC.
 29. FOR PAST
 40+ YRS.

ERRONEOUS DEED
 POSITION

NARRATIVE

THE PURPOSE OF THIS SURVEY WAS TO CORRECT THE ERRONEOUS DEED TO THE WELL SITE WHICH DESCRIBES A PARCEL 746.46 TOO FAR SOUTH. TO DETERMINE THIS WE FND. THE STONE FOR THE NE SEC. COR. OF 29 AND THE FENCE COR. AT THE SE SEC. COR., WHICH HAS BEEN THE RECOGNIZED SEC. COR. FOR THE LAST 40+ YRS. ACCORDING TO MR. DICK WILKINSON WHO OWNS MOST OF THE PROPERTY IN THE AREA. WE THEN RAN A LINE BETWEEN THE TWO SEC. COR. AND LOCATED THE FENCE AROUND THE WELL SITE.

RECEIVED BY

Morrow County Surveyor
 Date 6-15-83
 Rec'd By M.L.D.
 No. B-620-K

**REGISTERED
 PROFESSIONAL
 LAND SURVEYOR**

Earl D. Ming
**OREGON
 DEC. 14, 1979
 EARL D. MING
 1861**

WELL SITE #2 IN THE NE 1/4, SE 1/4 SEC. 29 T.3S. R.28E. W.M. MORROW CO.		
SCALE: 1" = 100'	APPROVED BY:	DRAWN BY <i>RMR</i>
DATE: 5-25-83		REVISED
FOR THE CITY OF HEPPNER		
R&M SURVEYORS AND CONSULTANTS INC. P.O. Box 395 BOARDMAN OR. 97818		DRAWING NUMBER 83-525

O DENOTES 5/8" X 30" IRON ROD SET