

frd P.K. nail

MAIN STREET

frd P.K. nail
el. = 1078.73

STREET



Set B.C. w/
el. = 1088.00

"Sperry's Second
Addition" Block 5

40

30

STREET

1156.00

"Sperry's Fourth
Addition" Block 3

30

5 STREET

Set B.C. w/
el. = 1078.28

frd 5/8" iron pin w/
alum. cap

75.00

frd 5/8" iron pin
w/alum. cap w/
el. = 1077.33

20

WILLOW CREEK

NARRATIVE:

The purpose of this survey is to establish the monuments in the City of Tione which could be used for elevations and horizontal control.

The section corner at the intersection of F Street and Main Street was a 1/2" i. pin which has been used in the past as noted on Morrow County Surveyor Drwg. Nos. 254-K and B-505-K.

The monument at Fifth and A Streets was set by using information from the Sperry's Addition. The pins set during the Mooney survey as shown on B-505-K were used to set the monument.

Elevations were run from USGS station G87 using elevation 1093.31.

- denotes found monument as noted
- denotes set Brass Cap with aluminum cap

K KRUMBEIN ENGINEERING LTD. ENGINEERS - SURVEYORS - PLANNERS 361 S.E. Second Pendleton, Oregon	Scale 1" = 50'	Drn. By MLD	Drng. No. 83-206	Revision 1
	Date 12-20-83	Ckd. By DHK	Job No. 83-134	Revision 2
Survey for MORROW COUNTY Tione, Oregon NW 1/4, NE 1/4, Sec. 9, T16, R24E, W.M.		REGISTERED PROFESSIONAL LAND SURVEYOR <i>David H. Krumbein</i> OREGON JULY 17, 1970 DAVID H. KRUMBEIN 533		RECEIVED BY Morrow County Surveyor Date <u>4-3-84</u> Rec'd By <u>MLD</u> No. <u>B-658-K</u> -238