

- denotes set $\frac{5}{8}$ " x 30" iron pin with aluminum cap stamped PLS 933
- denotes found PK nail, Morrow Co No. B-505-K
- ⊙ denotes found $2\frac{1}{2}$ " BC, Morrow Co No. B-658-K



NARRATIVE

The purpose of this survey was to establish the Southwest and Southeast corners of Block 24, Will's Addition to the City of Lane, Morrow County.

The South line of Block 24 is called for as being 100 feet North of the centerline of the UPRR. Points on the centerline of the existing tracks were established along 2000 feet of tracks and were used for the centerline. The West line of D Street and the East line of C Street were established from the found monuments on Main Street as shown. These points were set for Morrow Co Surveyor No B-505-K & B-658-K.

No bearings are shown as the plats have no bearings and show all streets at 90°.

KRUMBEIN ENGINEERING LTD. ENGINEERS - SURVEYORS - PLANNERS 361 S.E. Second Pendleton, Oregon	Scale $1\frac{1}{2} = 100'$	Drn. By MLD	Drng. No. 86-16B	Revision 1
	Date 7-7-86	Ckd. By OHR	Job No. 86-70	Revision 2
Survey for GALE GRAY Blk 24, Will's Addition, Lane SE $\frac{1}{4}$, SE $\frac{1}{4}$, Sec. 4, T15, R24E, W.M.				RECEIVED BY Morrow County Surveyor Date <u>10/4/86</u> Rec'd By <u>MLD</u> No. <u>B-844-K-258</u>