

FND. P.K. NAIL KRUMBEIN SURVEY NO. 76-15B

589°36'10" E

FND. RR SPIKE KRUMBEIN #76-12C

& KUNZE RD.

SET RR SPIKE MKD. LS1861

1321.14

BEARING BASIS

510.57

FND. R.R. SPIKE NORTH 1/4 COR. SEC. 20 HELD

RR SPIKE 2.15, 4.8W

20 FT

660.57

150.00

150.00

NEW 60 FT RIW LINE

40 FT RIW LINE

20 FT

50°30'30"W EAST LINE OF THE W 1/2 OF THE E 1/2 OF THE NW 1/4

50°30'30"W 300.00

NEW 1.03 AC. PARCEL

50°30'30"W 300.00

589°36'10" E 150.00

349.53

FND. 5/8" IRON ROD KRUMBEIN #76-12C

TAX LOT 300



### NARRATIVE:

THE PURPOSE OF THIS SURVEY WAS TO PARTITION A PARCEL 150.00 BY 300.00 IN THE NE COR. OF TAX LOT 300. DAVE KRUMBEIN SUBDIVIDED SEC. 20 IN A 1-14-76 SURVEY, DRWG. # 76-12C IN WHICH HE SET THE EAST LINE OF THE WEST 1/2 OF THE EAST 1/2 OF THE NW 1/4. THIS LINE IS THE WEST LINE OF THE PARCEL THAT I AM SURVEYING. DISTANCES AND ANGLES CHECK WELL SO I AM HOLDING THE SAME LOCATION AS DAVE KRUMBEIN

- DENOTES MON. FND. AS NOTED.
- DENOTES 5/8" x 30" IRON ROD & CAP MKD LS1861 SET
- ▲ DENOTES SPIKE MK'D LS1861 SET

SURVEYORS AND		SURVEY FOR: ARNOLD BRAAT	
<b>R &amp; M</b>		LOCATION: TAX LOT 300, SEC. 20, T. 4 N. R. 25 E.	
		W.M. MORROW CO. OR.	
CONSULTANTS, INC.		REGISTERED PROFESSIONAL LAND SURVEYOR	RECEIVED BY Morrow County Surveyor
P.O. BOX 709 IRRIGON, OR. 97844 PH: 922-3093			
SCALE 1" = 100'		Earl D. Ming	Rec'd By <u>DHK</u>
DATE 2-20-87			No. <u>B-849K-262</u>
DRWN BY EDM		OREGON DEC. 14, 1979 EARL D. MING 1861	
CHKD BY KJM			
REVISION NO			
DRWG NO. 87-220-1			