



This area was excavated by someone in the past. Krumbein's B.C. was removed but saved. I reset it in same location by using Krumbein's angles and distance values. See Krumbein's Survey dated 11-14-85 # D-725-K

Fd. Conc. Monu. 15" Underground. Set two-2" pipes on south side of Conc. Monu. so one can locate with pin finder.

RECEIVED BY
Morrow County Surveyor
Date 12/89
Rec'd By DE
No. B-891-E-282

LEGEND

- ⊙ ----- Found a monu. as shown
- ----- Set a monu. as shown
- ----- Monitoring Well
- (xxx) ----- Dist. or Bearing of Record
1906 Worthington Survey

NARRATIVE :

The purpose of this survey is to establish the south line of the N.E. 1/4 of the S.E. 1/4 of section 19, T5N, R27E, W.M. at Irrigon, Oregon to tie in and describe an easement around a monitoring well belonging to the City of Irrigon, Oregon. A field search was made and the monuments found are as shown on this map. Mr. Krumbein set a pipe with a brass cap on top in 1985 for the N.W. corner of the S.E. 1/4 of the S.E. 1/4 of the said section 19 and was later removed by excavation and laid on the ground and saved. By using Mr. Krumbein's survey information, I reset the same pipe and B.C. in the same location as Mr. Krumbein did using his angles and distances. From this I can now tie in the city's WELL "UB" and describe an easement around it. Bearing Base is the south line of said section 19 being S 89° 43' E as shown. Reference material used is as follows :

- 1) Krumbein's survey Co. # D-725-K
- 2) Edwards survey for Don Hurd B-885-E
- 3) Worthington's survey of 1906
- 4) Tam blyn's Plat of 1935 which is same as Worthington's of 1906

SCALE: 1" = 300'
DATE: 11-29-89

SURVEY FOR CITY OF IRRIGON, OR.
OF JOHN GORHAM'S SOUTH LINE
(N. Line of SE 1/4 of SE 1/4 of Sec. 19) T5N, R27E
For Monitoring Well Easement

SCALE: 1" = 300' DATE: 11-29-89

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Donald L. Staebler
OREGON
SEPT. 23, 1977
DONALD L. STAEBLER
#1333

Donald L. Staebler
ENGINEER - SURVEYOR
1532 SW 41 ST
Pendleton, Oregon 97801
Phone 276-7166