



Section Cor.  
 16 15  
 9 10  
 16 15  
 5.02°10'26\"/>

Section Cor.  
 16 15  
 21 22  
 5.02°10'26\"/>

Temporary Curbs etc  
 to be relinquished when  
 Road is extended

**Notes**

Indicates sat 5/8 x 24" Rebar  
 unless otherwise noted

**Curve Data**

No.	Δ	R	L	T
1	61°53'08"	130.08	140.50	
2	61°53'08"	70.08	75.70	
3	61°53'08"	100.08	108.10	60.00
4	58°08'40"	119.90	115.59	
5	58°08'40"	173.90	176.88	
6	58°08'40"	183.90	166.03	80.00
7	74°36'36"	122.95	82.88	
8	52°17'48"	162.95	108.73	80.00
9	07°40'10"	192.95	26.16	
10	19°55'02"	192.95	67.07	
11	36°08'58"	132.95	83.80	
12	16°08'58"	132.95	37.47	
13	50°41'23"	122.96	175.97	
14	50°40'23"	138.96	122.90	
15	57°40'23"	168.96	149.41	80.00

**Description**

A parcel of land situated in Sections 15 and 16, Township 4 North, Range 22 East, W.M. Morrow County, Oregon, more particularly described as follows:

Beginning at the Northwest corner of said Section 15; Thence 5.82°10'26" along the West line of said Section 15, a distance of 1904.84 feet, more or less to a point on the Southwesterly margin of Union Pacific Railroad right-of-way and True Point of Beginning; Thence N 61°09'16" along said Southwesterly margin a distance of 846.36 feet to a point on the westerly margin of Tower Road right-of-way; Thence S 07°40'00" along said westerly margin a distance of 266.89 feet to a point on the Northerly margin of US Interstate 80-N right-of-way; Thence S 60°37'55" along said Northerly margin a distance of 592.37 feet; Thence continuing along said Northerly margin, S 82°26'00" at a distance of 1990.15 feet to a point on the West line of said Section 15; Thence continuing S 82°26'00" along said Northerly margin a distance of 995.96 feet; Thence N 07°40'23", a distance of 613.15 feet to a point on the Southwesterly margin of Union Pacific Railroad right-of-way; Thence N 61°09'16" along said Southwesterly margin a distance of 1051.34 feet to a point on the East line of said Section 16 and the True Point of Beginning.

Containing 44.072 acres.  
 Subject to easements, reservations and restrictions of record

Scale 1"=200'

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR  
 Richard H. Rogers  
 9-76

C-27-K-302

ROGERS SURVEYING INC. P.S.		Boeing Agri-Industrial Co.	
PROFESSIONAL LAND SURVEYORS		PROJECT	
P.O. Box 307 Richland, Washington Phone (509) 943-3151		Record Survey	
DATE	SCALE	SHEET	OF
2-18-77	1"=200'	970	1