



**NOTES:**

Bearings are based on survey plot drawing done by the U.S. Department of the Interior General Land Office, dated February 21, 1941. All bearings do not match the BLM. I used the bearings between the East one-quarter and Southeast corner of Section 10, Township 5 South, Range 28 East, W.M. All bearings and distances are true. This drawing is one section out of five sections surveyed for the U.S. Forest Service.

All field notes on traverses for Section 3 are in Book 2. Notes used to set Brass Caps are in Book 2, pages 186-199. Accessory ties for all corners set are described in Certified Record of Land Monumentation.

All found corners are part of a closed traverse. See Traverse Detail Sheet 6 of 6. Computations for all corners set are based on the Manual of Surveying Instruction 1973, Chapter 5.

All lines posted were performed by the Offset Method from the traverse lines.

**LEGAL DESCRIPTION**

U.S. Forest Service ownership; all of Section 3, excepting the South half of the Northwest one-quarter and the North half of the Southwest one-quarter of Section 3, Township 5 South, Range 28 East of the Willamette Meridian, County of Morrow.

I, Terry E. Hamby, a registered land surveyor in the State of Oregon, hereby certify that this plat and the notes hereon, or attached, are a correct representation of a survey I performed during June thru October, 1979, for the U.S. Forest Service in accordance with the statutes of the State of Oregon and with the Articles of my contract.

Terry E. Hamby (s) Terry E. Hamby  
Registered Land Surveyor  
Oregon License No. 1638



RECEIVED BY  
Morrow County Surveyor  
Date 10-10-79  
Acc'd ymms  
NC # 266-R

- denotes Brass Cap set
- denotes Brass Cap found, set BLM 1939
- ( ) denotes GLO record bearings & distances, 1939
- denotes Forest Service Boundary & posted line

Sheet 1 of 6

<b>KRUMBEIN ENGINEERING CO.</b> ENGINEERS - SURVEYORS - PLANNERS 221 S. Main, Pendleton, Oregon	SCALE 1" = 500'
	DATE Dec. 4, 1979
Survey for <b>U.S. FOREST SERVICE</b> Section 3, T5S, R28E, W.M.	DRN BY MH
	CKD BY T.E.H.
	DRNG NO. 79-73C

C-266-K-414